



Central Plains Cement Company

Cement Mill Test Report

Month of Issue: July-17

Plant: Sugar Creek Plant
 Product: Portland Cement Type I-II (MH)
 Shipped: Jun-17
 Manufactured: Jun-17

The current version of ASTM C 150 and AASHTO M 85 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Rapid Method, X-Ray (C 114)			Air content of mortar (%) (C 185)		
SiO2 (%)	---	20.3		12 max	8
Al2O3 (%)	6.0 max	4.7	Blaine Fineness (m2/kg) (C 204)		
Fe2O3 (%)	6.0 max	3.1		260 - 430	355
CaO (%)	---	64.0	-325 (%) (C 430)		
MgO (%)	6.0 max	1.2		---	95.7
SO3 (%)	3.0 max *	3.0	Autoclave expansion (%) (C 151)		
Loss on ignition (%)	3.5 max	2.5		0.80 max	-0.01
Insoluble residue (%)	1.5 max	0.47	Compressive strength (PSI) (C 109)		
CO2 (%)	---	1.7		---	2100
Limestone (%)	5.0 max	4.3	1 day		3750
CaCO3 in Limestone (%)	70 min	92	3 days	1740 min	5050
Adjusted Potential Phase Composition (C 150)			7 days	2760 min	6920
C3S (%)	---	54	28 days (Reflects previous month's data)	---	6920
C2S (%)	---	18	Time of setting (minutes)		
C3A (%)	8 max	7	Vicat Initial (C 191)	45 - 375	99
C4AF (%)	---	9	Mortar Bar Expansion (%) (C 1038)*		
C3S+4.75*C3A (%)	100 max	89		0.020 max	0.005
			Specific Gravity (C188)		
				---	3.15

ASTM C 150-16 and AASHTO M 85-16 Optional Chemical Requirements:

NaEq (%) 0.60 max 0.55

* May exceed 3.0% SO3 maximum based on our C 1038 results of <0.02% expansion at 14 days.

We certify that the above described cement meets the chemical and physical requirements of Type I and Type II (MH) for the current version of ASTM C 150 & AASHTO M 85 STANDARD.

Sugar Creek Plant
 2200 N Courtney Rd.
 Sugar Creek, MO 64050
 816-257-3608

Certified By:

Paul Engel - Quality Coordinator

7/10/2017



Central Plains Cement Company

Cement Mill Test Report

Month of Issue: July-17

Plant: Sugar Creek Plant
Product: Portland Cement Type I-II (MH)
Shipped: Jun-17
Manufactured: Jun-17

The current version of ASTM C 150 and AASHTO M 85 Standard Requirements

Base Cement Phase Composition

<u>Item</u>	<u>Test Result</u>
C3S (%)	57
C2S (%)	18
C3A (%)	8
C4AF (%)	10

We certify that the above described cement meets the chemical and physical requirements of Type I and Type II (MH) for the current version of ASTM C 150 & AASHTO M 85 STANDARD.

Sugar Creek Plant
2200 N Courtney Rd.
Sugar Creek, MO 64050
816-257-3608

Certified By:

Paul Engel - Quality Coordinator

7/10/2017